



Open Sea Operating Experience to Reduce Wave Energy Costs

Deliverable D1.3

Online Data Query Tool

| | |
|---------------------|---------------------------|
| Lead Beneficiary | Idom |
| Delivery date | 2019-07-29 |
| Dissemination level | Public |
| Status | Approved |
| Version | 1.0 |
| Keywords | Open Sea, Instrumentation |



This project has received funding from the European Union's Horizon 2020 research and innovation programme under grant agreement No 654444

D1.3

Online Data Query Tool

Disclaimer

This Deliverable reflects only the author's views and the Agency is not responsible for any use that may be made of the information contained therein

Document Information

| | |
|-------------------------------|--|
| Grant Agreement Number | 654444 |
| Project Acronym | OPERA |
| Work Package | WP 1 |
| Task(s) | T1.4 |
| Deliverable | D1.3 |
| Title | Online Data Query Tool |
| Author(s) | Endika Aldaiturriaga (Idom), François-Xavier Fäy (Tecnalia) |
| File Name | OPERA_D1.3_Online Data Query Tool_IDOM_20190729_v1.0.docx |

Change Record

| Revision | Date | Description | Reviewer |
|-----------------|-------------|--------------------------|----------------------|
| 0.1 | 22/07/2019 | Partial Draft | Endika Aldaiturriaga |
| 0.2 | 23/07/2019 | Full draft | WP1 partners |
| 0.5 | 24/07/2019 | Version for peer-review | UEDIN, Coordinator |
| 1.0 | 29/07/2019 | Final version for the EC | EC |

EXECUTIVE SUMMARY

The main objective of WP1 is to ensure state of the art instrumentation is installed and operates as planned in the harsh open-sea environment, enhancing successful development of the technical work of other Work Packages.

This is articulated in the following specific objectives:

- Assessment of data requirements from other Work Packages in relation to previous/existing research and operational infrastructure for the test to be completed in Mutriku Wave Power Plant and IDOM's WEC. (Completed in Task 1.1)
- Deployment of robust and state-of-the-art instrumentation system for the fulfilment of the above requirements. Development of a failure risk matrix and contingency plan for the systems comprising the instrumentation and monitoring system. (Completed in Task 1.2)
- Provision of a structured access for other Work package partners to the research data produced according to the Project Data Management Plan. (Completed in Task 1.4)

The present document aims to support the Online Data Query Tool Software containing the specific datasets regarding biradial turbine and Control Law testing, collected during the BiMEP testing campaign of the OPERA project. The Online Data Query Tool will provide an open access to the operating data after the project is finished. The final outcome of Task 1.4 has provided partners within the consortium structured data access for the assessment of the innovations proposed during the project lifetime. The query tool offers an easy way to download available data from BiMEP testing campaign from the open-access repository ZENODO.

TABLE OF CONTENTS

| | |
|---|----|
| EXECUTIVE SUMMARY | 3 |
| TABLE OF CONTENTS | 4 |
| LIST OF FIGURES | 5 |
| LIST OF TABLES | 6 |
| ABBREVIATIONS AND ACRONYMS | 7 |
| 1. INTRODUCTION | 8 |
| 2. PTO TESTING CAMPAIGN | 10 |
| 2.1 INTRODUCTION | 10 |
| 2.2 PTO TESTING CAMPAIGN..... | 11 |
| 2.3 OPERATIONAL DATA TABLE | 12 |
| 2.3.1 DATA QUALITY..... | 13 |
| 3. PROCESS INSTRUMENTATION/SIGNAL LIST | 14 |
| 4. CONCLUSIONS | 16 |
| 5. REFERENCES | 17 |
| 6. ANNEX I: TURBINE INSTRUMENTATION..... | 18 |
| 7. ANNEX II: EQUIPMENT/SIGNAL LIST FOR BiMEP TESTING CAMPAIGN | 19 |

LIST OF FIGURES

FIGURE 2-1 MARMOK-A-5 DEVICE DEPLOYED IN BIMEP 10
FIGURE 2-2 BIMEP TEST SITE BATHYMETRY AND WEC LOCATION 11
FIGURE 2-3. GENERAL VIEW OF THE ONLINE DATA QUERY TOOL..... 12
FIGURE 2-4. DETAILED VIEW OF ONLINE DATA QUERY TOOL 13
FIGURE 6-1: SCHEMATIC REPRESENTATION OF THE BIRADIAL TURBINE ASSEMBLED INTO THE
IDOM MARMOK-A-5 SPAR-BUOY AND KYMANER'S PRESSURE TAPS NOMENCLATURE. 18

LIST OF TABLES

TABLE 1-1: DATASET DEFINED IN DATA MANAGEMENT PLAN, SUPPORTING DELIVERABLES AND PUBLISHED DATASETS..... 8

TABLE 2-1: DATA QUALITY INDICATOR SIGNALS..... 13

TABLE 3-1: DATABASE COLUMN MATCHING TO SIGNAL LIST 14

TABLE 7-1: EQUIPMENT/SIGNAL LIST FOR BIMEP TESTING CAMPAIGN..... 19

ABBREVIATIONS AND ACRONYMS

| | |
|-------|---|
| BIMEP | Biscay Marine Energy Platform |
| CL | Control Law |
| HSSV | High Speed Switching Valve |
| LCOE | Levelized Cost of Energy |
| OPERA | Open Sea Operating Experience to Reduce Wave Energy Costs |
| OWC | Oscillating Water Column |
| PLC | Programmable Logic Controller |
| PTO | Power Take-Off |
| RMS | Root Mean Square |
| TRL | Technology Readiness Level |
| VFD | Variable Frequency Drive |
| WEC | Wave Energy Converter |

1. INTRODUCTION

In the scope of the OPERA project, the objective of Work Package 1 (WP1) is to provide seamless data collection and storage, enhancing successful development of the technical work of other Work Packages. WP1 has the final goal of reducing the time to market wave energy, by advancing in four key innovations aiming to reduce up to 50% the Levelized Cost of Energy (LCOE) projections of a floating Oscillating Water Column (OWC) technology.

The purpose of this deliverable is to provide a guidance on data access and interpretation, with the aim of having Findable, Accessible, Interoperable and Reusable data according to the guidelines establish in Deliverable 8.7: Data Management Plan.

Chapter 2 in this document provides a general view of the testing campaign undergone and presents the operational data table to be published in ZENODO repository. Chapter 3 provides a column-wise explanation of the data contained in the table, aiming to facilitate comprehension of the data by any potential reader, with this information being further expanded in the Annexes of the document. A set of final conclusions are drawn in Chapter 4, outlining the outcomes of Task 1.4.

The Online Data Query Tool, developed in the scope of Task 1.4, has been implemented in Excel and offers an easy way to access all the open-access data available from BiMEP testing campaign. It contains the centrepiece information for PTO and Control Law assessment and allows the user to further analyse operational data by using the standard tools provided by MS Excel.

Other datasets described in Deliverable D8.7 has been discarded, as they are published in ZENODO or referenced in the corresponding deliverables as shown in **¡Error! No se encuentra el origen de la referencia..**

TABLE 1-1: DATASET DEFINED IN DATA MANAGEMENT PLAN, SUPPORTING DELIVERABLES AND PUBLISHED DATASETS.

| D8.7 Dataset | Supporting Deliverable(s) | Link to ZENODO dataset (If Applicable) |
|-----------------------------|----------------------------------|---|
| DS_Wave_Mutriku | | https://doi.org/10.5281/zenodo.1478564 |
| DS_Wave_BiMEP | | https://doi.org/10.5281/zenodo.1311593 |
| DS_Tethers_Lab | D2.3 | |
| DS_Mooring_BiMEP | D2.2 | |
| DS_Biradial_Turbine_Lab | D3.2 | |
| DS_Power_Output_Lab | D4.1 | |
| DS_Biradial_Turbine_Mutriku | D3.3, D4.2 | https://doi.org/10.5281/zenodo.3228108 |
| DS_Power_Output_Mutriku | | |

D1.3

Online Data Query Tool

| | | |
|---------------------------|---------------------|---|
| DS_Biradial_Turbine_BiMEP | D3.4, D4.3, D1.3 | https://doi.org/10.5281/zenodo.3349538 |
| DS_Power_Output_BiMEP | | |
| DS_Power_Quality_Lab | D5.2, D5.4 | https://doi.org/10.5281/zenodo.3250832 |
| DS_Power_Quality_Mutriku | | |
| DS_Offshore_Operations | D6.3 | |

2. PTO TESTING CAMPAIGN

2.1 INTRODUCTION

IDOM's MARMOK-A-5 device is a spar type OWC wave energy converter buoy. It has a diameter of 5 m and is 42 m long. MARMOK-A-5 has been deployed during almost three years continuously in BiMEP. It was first deployed at BiMEP prior to the OPERA project, mounting two Wells turbines of 15 kW rated power each (baseline configuration).



FIGURE 2-1 MARMOK-A-5 DEVICE DEPLOYED IN BIMEP

The buoy can be divided into three parts: the floater which adds floatability and holds all the electrical equipment and sensors including umbilical cable entry for grid connection; the central cylinder which holds the inner water column; and the water ballast tank which can be partially or fully emptied for buoy installation/decommissioning.

Two major innovations undertaken during the OPERA project are the design, construction and testing of a novel biradial turbine, and the development and testing of innovative Control Laws to enhance power production. Following an extensive testing campaign in the Mutriku OWC plant, the biradial turbine was installed on top of the MARMOK-A-5 buoy (refitted prototype) in summer 2018 and served as Control Law testing platform during 2019.

BiMEP is an infrastructure which purpose is to test prototypes of marine energy collectors and auxiliary equipment in the open sea. It is located off the coast at Armintza in Spain, and consist of 5.2 km², restricted to shipping with perimeter beacons. The depth in the site goes from 50 to 90 meters and the seabed is mostly sandy with rocky areas. Figure 2-2 shows the BiMEP site with the location of the MARMOK-A-5 mooring perimeter, with the WEC in the center.




FIGURE 2-2 BIMEP TEST SITE BATHYMETRY AND WEC LOCATION

2.2 PTO TESTING CAMPAIGN

The acquired data in the open-sea tests has granted valuable information for the OPERA project. Recorded data of power production, power quality, efficiency, mooring force data, and other aspects such as electrical grid integration certainly play a significant role in ocean energy technology development.

The assessment of the biradial turbine performance has been analysed in-depth in Deliverable D3.4. A set of analysis and post processing criteria were proposed to facilitate performance assessment, down-selecting some representative tests cases from the whole set of tests produced during the project.

On the other hand, D4.3 uses the same criteria and analyses their impact in Control Law performance evaluation. It leaves open the modification of the criteria to have a more even distribution of test cases across several Control Laws and to assess their strong and weak points.

D1.3 Online Data Query Tool

| Test Runs | WEC State | | Air Chamber Pressure Sensors - Standard Deviation [Pa] | | | |
|----------------------------------|-----------|-----------|--|------------------|------------------|------------------|
| | TestId | WEC State | Control Law | Pressure 1A [Pa] | Pressure 2A [Pa] | Pressure 3A [Pa] |
| 0004d0b59e19461ff126e3a08a814c33 | Running | 6 | 2301,83 | 2324,07 | 2302,24 | 2276,35 |
| 004114607c92d2124a67ea0f4cb5f85 | Running | 2 | 794,81 | 809,83 | 795,26 | 789,24 |
| 006f52e9102a8d3be2fe5614f42ba989 | Running | 1 | 2142,54 | 2171,88 | 2142,95 | 2120,29 |
| 008bd5ad33b754d500338c253d9c1770 | Running | 6 | 4259,01 | 4319,76 | 4260,04 | 4216,99 |
| 00a03ec6533ca715e644d198d815323c | Running | 1 | 4116,71 | 4164,71 | 4116,83 | 4074,15 |
| 00ac8ed3b4327bdd4ebbebc2ba10a00 | Running | 2 | 773,88 | 788,65 | 780,18 | 772,97 |
| 00e26af6ac3b1c1c49d7c3d79c60d000 | Running | 2 | 4846,50 | 4945,61 | 4848,26 | 4812,15 |
| 00ec53c4682d36f5c4359f4ae7bd7ba1 | Running | 2 | 921,00 | 939,11 | 921,47 | 914,62 |
| 01161aaa0b6d1345dd8fe4e481144d84 | Running | 1 | 2896,29 | 2954,09 | 2897,93 | 2871,84 |
| 01386bd6d8e091c2ab4c7c7de644d37b | Running | 1 | 919,01 | 933,74 | 920,22 | 911,29 |
| 013a006f03dbc5392effeb8f18fda755 | Running | 1 | 2233,20 | 2269,08 | 2234,17 | 2212,78 |
| 013d407166ec4fa56eb1e1f8cbe183b9 | Running | 1 | 1497,82 | 1525,01 | 1498,79 | 1485,20 |
| 01882513d5fa7c329e940dda99b12147 | Running | 1 | 1363,44 | 1380,17 | 1363,93 | 1351,07 |
| 01894d6f048493d2cacde3c579c315a3 | Running | 6 | 1310,90 | 1327,03 | 1311,63 | 1306,35 |
| 018b53ce1fd616d874afad0f44ba338d | Running | 1 | 1983,85 | 2020,03 | 1985,05 | 1967,02 |
| 01931a6925d3de09e5f87419d9d55055 | Running | 6 | 2703,22 | 2745,84 | 2704,80 | 2678,11 |
| 019d385eb67632a7e958e23f24bd07d7 | Running | 2 | 387,04 | 393,86 | 387,63 | 383,72 |
| 01d8bae291b1e4724443375634ccfa0e | Running | 1 | 804,39 | 817,28 | 805,03 | 797,44 |
| 01e002f4bfcbb7505cb641066f2859b | Running | 1 | 2604,94 | 2648,09 | 2606,21 | 2581,06 |
| 01e9565ecc4e989123f9620c1d09c09 | Running | 1 | 1131,60 | 1151,70 | 1132,55 | 1122,66 |
| 01eee509ee2f68dc6014898c309e86bf | Running | 1 | 1296,64 | 1316,73 | 1297,58 | 1287,32 |
| 01f78be6f7cad02658508fe4616098a9 | Running | 1 | 377,14 | 384,16 | 377,76 | 374,12 |
| 020bf2c45e7bb322f89a226bd2c5d41b | Running | 6 | 1649,89 | 1665,82 | 1650,38 | 1632,34 |
| 020c8bfac8de160d4c5543b96d1fdede | Running | 1 | 1944,30 | 1976,76 | 1945,16 | 1927,08 |
| 021b8c7ee20b71134d53e20206bd6feb | Running | 2 | 1207,31 | 1229,19 | 1208,67 | 1197,58 |
| 0233f3bb964cf325a30f8b1c2ed2da93 | Running | 6 | 893,45 | 904,38 | 894,28 | 885,48 |
| 0234c510be6d908b28c70ff313743079 | Running | 1 | 4032,01 | 4101,48 | 4033,61 | 3995,39 |
| 0245952ecff55018e2a459517db40e3 | Running | 1 | 1885,28 | 1917,50 | 1887,31 | 1868,68 |
| 024d7f84ff11dd7e8d9c510137a2381 | Running | 2 | 1816,80 | 1850,21 | 1817,88 | 1801,18 |

FIGURE 2-4. DETAILED VIEW OF ONLINE DATA QUERY TOOL

2.3.1 DATA QUALITY

Data Quality markers were introduced during the data acquisition process. The timeseries values include a numerical quality indicator, ranging from 0 to 192. This indicator is automatically assigned by the acquisition system.

TABLE 2-1: DATA QUALITY INDICATOR SIGNALS

| Decimal value | Quality Indicator |
|---------------|--|
| 0 | Bad |
| 8 | Bad - Not Connected |
| 12 | Bad - Device Failure |
| 16 | Bad - Sensor Failure |
| 20 | Bad - Last Know Value Passed |
| 24 | Bad - Comm Failure |
| 64 | Uncertain |
| 68 | Uncertain - Last Usable Value - timeout of some kind |
| 80 | Uncertain - Sensor not Accurate - outside of limits |
| 192 | Good |

With the objective of proving the highest quality data possible, all the tests contained in the published dataset are strictly required to have a Good quality indicator, ensuring all sensor and systems provide accurate readings.

3. PROCESS INSTRUMENTATION/SIGNAL LIST

TABLE 3-1 enumerates the list of available instruments and signals as built for the tests in the MARMOK-A-5 device for the testing campaign carried out in the OPERA Project.

TABLE 3-1: DATABASE COLUMN MATCHING TO SIGNAL LIST

| BiMEP PTO and Control Law Testing Data | | |
|---|------------------------|--|
| COMMENT | Signal in Table | Comments |
| Test Id | | Test Number Identifier. Helps identifying test bins |
| WEC State | S.08.01 | Current State of PLC State Machine: 1: Booting 2: Standby 3: Spin-up 4: Running 5: Spin-down 6: Safe Standby |
| Chamber pressure 1A | P.02.01P.02.01 | RMS value of chamber pressure sensor, position 1 |
| Chamber pressure 2A | P.02.02 | RMS value of chamber pressure sensor, position 1 |
| Chamber pressure 3A | P.02.03 | RMS value of chamber pressure sensor, position 2 |
| Chamber pressure 3B | P.02.04 | RMS value of chamber pressure sensor, position 3 |
| PTO Built-in Pressure Sensor P1 | P.04.02 | RMS value of pressure sensor p1. See turbine diagram in Annex |
| PTO Built-in Pressure Sensor P2 | P.04.03 | RMS value of pressure sensor p2. See turbine diagram in Annex |
| PTO Built-in Pressure Sensor P3 | P.04.04 | RMS value of pressure sensor p3. See turbine diagram in Annex |
| PTO Built-in Pressure Sensor P4 | P.04.05 | RMS value of pressure sensor p4. See turbine diagram in Annex |
| PTO Built-in Pressure Sensor P5 | P.04.06 | RMS value of pressure sensor p5. See turbine diagram in Annex |
| PTO Built-in Pressure Sensor P6 | P.04.07 | RMS value of pressure sensor p6. See turbine diagram in Annex |
| PTO Built-in Pressure Sensor P7 | P.04.08 | RMS value of pressure sensor p7. See turbine diagram in Annex |
| PTO Built-in Pressure Sensor P8 | P.04.09 | RMS value of pressure sensor p8. See turbine diagram in Annex |
| HSSV Position | C.04.01 | HSSV valve position as the average of the position of the 4 actuators of that control the valve, in mm. 61 is fully open |
| HSSV Position | C.04.01 | Standard deviation of valve aperture |
| Drive 1 Speed Feedback | S.03.01 | Average Generator Speed measurement through the generator encoder. |
| Drive 1 Speed Feedback | S.03.01 | Standard deviation of Generator Speed measurement through the generator encoder. |
| Generator Temp 1 | T.03.01 | Average Generator stator temperature value measured in winding 1 |
| Generator Temp 2 | T.03.02 | Average Generator stator temperature value measured in winding 2 |
| Generator Temp 3 | T.03.03 | Average Generator stator temperature value measured in winding 3 |

D1.3

Online Data Query Tool

| BIMEP PTO and Control Law Testing Data | | |
|--|------------------------|---|
| COMMENT | Signal in Table | Comments |
| Drive 1 Active Current | S.06.01 | Average active current flowing to/from the generator. |
| Drive 1 Active Current | S.06.01 | Standard deviation of active current flowing to/from the generator. |
| Drive 1 Torque Ref | S.06.01 | Average Torque reference as % of nominal demanded by the PLC to the VFD |
| Drive 1 Torque Ref | S.06.01 | Standard deviation of Torque reference as % of nominal demanded by the PLC to the VFD |
| Drive 1 Out Power | S.06.01 | Average estimated VFD electrical power as measured in the Drive terminals. |
| Drive 1 Out Power | S.06.01 | Standard deviation of VFD electrical power as measured in the Drive terminals. |
| Average Torque Slope for CL1 | S.08.01 | Torque Law Slope coefficient for CL1 |
| Average Torque Exponent for CL1 | S.08.01 | Torque Law Exponent coefficient for CL1 |
| Average Torque/pressure coefficient for CL2 | S.08.01 | Torque Law Torque/Pressure coefficient for CL2 |
| Average FeedForward term for CL1 | S.08.01 | Torque Law Feedforward coefficient for CL2 |
| Average Torque Slope for CL6 | S.08.01 | Torque Law Slope coefficient for CL6 |
| Average Torque Exponent for CL6 | S.08.01 | Torque Law Exponent coefficient for CL6 |

4. CONCLUSIONS

The ambitious instrumentation and SCADA systems planned and deployed for field testing within the OPERA project have provided satisfactory results. This entailed:

- Building an homogeneous data acquisition system to incorporate all the operational data produced in the project and provide seamless access tools for every partner to access the data.
- Adequately instrumenting the innovations tested under the scope of the projects (elastomeric tethers, shared mooring configuration, biradial turbine and Control Laws) to ensure sufficient data was gathered for the technical assessment of their potentialities.
- Providing high-quality environmental information data, including real-time wave elevation information both for Mutriku and BiMEP to feed predictive Control Laws;

The testing campaign in Mutriku offered a good opportunity to validate the data acquisition system and the tool for data access and sharing between the project partners. It also allowed the publication of various datasets as established in D8.7, Data Management Plan.

Lessons learnt and feedback from partners were incorporated into the design of the SCADA system deployed in BiMEP, allowing to build on existing equipment and systems used during the deployment phase prior to the OPERA project.

5. REFERENCES

- [1] Technical Note: "WP1-62600-30 Data Needs". OPERA Project.
- [2] Technical Note: "CORES sensor Recommendations". OPERA Project.
- [3] Technical Note: "PTO Instrumentation". OPERA Project.
- [4] Deliverable D3.4: "Open-sea performance and reliability of the OWC turbine and electrical equipment"
- [5] Deliverable D4.3: "Floating OWC control algorithms"
- [6] Deliverable D8.7: "Data Management Plan"

7. ANNEX II: EQUIPMENT/SIGNAL LIST FOR BIMEP TESTING CAMPAIGN

TABLE 7-1: EQUIPMENT/SIGNAL LIST FOR BIMEP TESTING CAMPAIGN

| Device ID | Signal Id | Signal | Resolution | Sensor Scale | Scan Rate |
|--|---|--------------------|------------|----------------|-----------|
| Area 02: Air Chamber in the WEC | | | | | |
| P.02.01 | Air pressure inside chamber | | | | |
| | P.02.01.001 | Pressure Signal | 0,005 bar | ±0.2 bar Gauge | 4 Hz |
| P.02.02 | Air pressure inside chamber | | | | |
| | P.02.02.001 | Pressure Signal | 0,005 bar | ±0.5 bar Gauge | 4 Hz |
| P.02.03 | Air pressure inside chamber | | | | |
| | P.02.03.001 | Pressure Signal | 0,005 bar | ±0.2 bar Gauge | 4 Hz |
| P.02.04 | Air pressure inside chamber | | | | |
| | P.02.04.001 | Pressure Signal | 0,005 bar | ±0.5 bar Gauge | 4 Hz |
| Area 03: Generator Nacelle | | | | | |
| T.03.01 | Temperature in Generator winding | | | | |
| | T.03.01.001 | Temperature Signal | 0.1 C° | 0..200 °C | 4 Hz |
| T.03.02 | Temperature in Generator winding | | | | |
| | T.03.02.002 | Temperature Signal | 0.1 C° | 0..200 °C | 4 Hz |
| T.03.03 | Temperature in Generator winding | | | | |
| | T.03.03.003 | Temperature Signal | 0.1 C° | 0..200 °C | 4 Hz |
| S.03.01 | Generator Shaft Rotational Speed | | | | |
| | S.03.01.001 | Encoder Signal | 0.1 rpm | 0..4500 rpm | 4 Hz |
| Area 04: Turbine | | | | | |
| P.04.02 | Air pressure at the trailing edge of the guide vanes (A) | | | | |
| | P.04.02.001 | Pressure Signal | 0,002 bar | ±0.2 bar Gauge | 4 Hz |
| P.04.03 | Air pressure at the trailing edge of the guide vanes (B) | | | | |
| | P.04.03.001 | Pressure Signal | 0,005 bar | ±0.5 bar Gauge | 4 Hz |
| P.04.04 | Air pressure at the trailing edge of the guide vanes (A) | | | | |
| | P.04.04.001 | Pressure Signal | 0,002 bar | ±0.2 bar Gauge | 4 Hz |
| P.04.05 | Air pressure at the trailing edge of the guide vanes (B) | | | | |
| | P.04.05.001 | Pressure Signal | 0,005 bar | ±0.5 bar Gauge | 4 Hz |
| P.04.06 | Air pressure at the stator minimum radius (C) | | | | |
| | P.04.06.001 | Pressure Signal | 0,002 bar | ±0.2 bar Gauge | 4 Hz |
| P.04.07 | Air pressure at the stator minimum radius (D) | | | | |

| Device ID | Signal Id | Signal | Resolution | Sensor Scale | Scan Rate |
|-----------------------------------|--|-------------------------------|------------|------------------|-----------|
| | P.04.07.001 | Pressure Signal | 0,005 bar | ±0.5 bar Gauge | 4 Hz |
| P.04.08 | Air pressure at the stator minimum radius (C) | | | | |
| | P.04.08.001 | Pressure Signal | 0,002 bar | ±0.2 bar Gauge | 4 Hz |
| P.04.09 | Air pressure at the stator minimum radius (D) | | | | |
| | P.04.09.001 | Pressure Signal | 0,005 bar | ±0.5 bar Gauge | 4 Hz |
| C.04.01 | HSSV valve continuous position | | | | |
| | C.04.01.001 | Latching Valve Position | 0.1 mm | 0..61 mm | 4 Hz |
| Area 06: Power Electronics | | | | | |
| S.06.01 | Power Electronics | | | | |
| | S.06.01.004 | Active Current | 0.1 A | 0..100% of Rated | 4 Hz |
| | S.06.01.007 | Output Power | 1 W | 0..100% of Rated | 4 Hz |
| Area 8: Machinery Room | | | | | |
| S.08.01 | Control System | | | | |
| | S.05.01.001 | WEC State | - | - | 4 Hz |
| | S.05.01.002 | Torque Reference | 0.1Nm | 0..100% of Rated | 4 Hz |
| | S.05.01.003 | Torque Slope for CL1 | - | - | 4 Hz |
| | S.05.01.004 | Torque Exponent for CL1 | - | - | 4 Hz |
| | S.05.01.005 | Torque/pressure coeff for CL2 | - | - | 4 Hz |
| | S.05.01.006 | FeedForward term for CL1 | - | - | 4 Hz |
| | S.05.01.007 | Avg Torque Slope for CL6 | - | - | 4 Hz |
| | S.05.01.008 | Avg Torque Exponent for CL6 | - | - | 4 Hz |